

KOZHIKODE DISTRICT CRICKET ASSOCIATION

NAME OF WORK : CONSTRUCTION OF INDOOR NET FACILITY AT SRI. GUJARATI VIDYALAYA HIGHER SECONDARY SCHOOL, KOZHIKKOD

TENDER SCHEDULE

Item No	Quantity	Unit	Details of work	Unit	Rate		Amount
					in figures	in words	
1	1.00	m3	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or leaner mix (i/c equivalent design mix)	/cum			
2	13.00	m3	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains, including dressing of sides and ramming of bottoms, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m and lift upto 1.5m.	/cum			
3	26.00	m3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 20 mm nominal size) - (Cement consumption - 320 kg/m3)	/cum			

4	73.00	m2	Centering and shuttering including strutting, propping etc. and removal of form work for Foundations, footings, bases for columns	/sqm			
5	850.00	kg	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level - Thermo-Mechanically Treated bars of grade Fe-500D or more.	/kg			
6	240.00	m2	15 mm cement plaster on rough side of single or half brick wall of mix: 1:4 (1 cement: 4 coarse sand)	/sqm			
7	3000.00	kg	Steel work in built up tubular (round tubes) trusses with straight or curved profiles as per design etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.	/kg			
8	225.00	m2	Providing trafford, coloured Aluminium sheet roofing 0.46 mm thick of approved make (Jindal, Hindalco, Oralium etc) including vertical or curved surface, cost of materials, labour etc complete as per the direction of departmental officers at site	/sqm			
9	52.00	m	Providing and fixing 150 mm pvc gutter with necessary clamps, screws, fixing and welding charges etc. complete as per the direction of Engineer in charge	/m			

10	175.00	m2	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete on steel work	/sqm			
11	2.00	nos	Providing and fixing gates at ends with GI rectangle tubes , weld mesh including cost of all materials and labour charges etc. complete as per the direction of Engineer in charge	/no			
12	580.00	m2	Supplying and providing 2.5 mm braided , 40 mm square HDPE net including cost of all materials, conveyance charges, labour charges for fixing et. Complete as per the direction of Engineer in charge.	/sqm			

Name and signature of
Contractor:

Address of Contractor

Note: 1. The rates quoted should be of excluding GST

2. All statutory deductions such as IT, Cess, K.C.W.W.F etc. will be made from the bill