

<b>KERALA CRICKET ASSOCIATION</b>					
KCA COMPLEX, TC 24/131(1), Shasthamkovil Road, Thycaud, TRIVANDRUM -695014					
SCHEDULE OF WORK -1. Tender No. KCA/EL/01/2021 Sub Sch.2 dt.16.12.2021					
PREVENTIVE MAINTENANCE OF FLOOD LIGHTS AND CONNECTED ELECTRICAL SYSTEMS AT GREEN FIELD STADIUM THIRUVANANTHAPURAM					
SI No	Description	Unit	Qty	Rate	Amount
<b>Mandatory requirements for improving the LUX output at the site</b>					

## Supply and Fixing Charges - Floodlight Components

i	Supply and fixing of HQI-TS2000W Bulbs in the existing Floodlight units. Make : OSRAM/ Equivalent.	Nos.	196		
l	Supply and providing Heat Resistant Toughned Glass - as required for replacement of Broken Glass in the lamp fixtures	Nos.	8		

## 2.0 Supply - Panel Components

q	Supply and Providing 250A 4P 25KA MCCB with terminal spreaders, Shunt trip coil- Compatible with existing Panel - L&T/ GE Make preferred (subject suitable to rotary handle availability)	Nos	01		
r	Supply and Providing 63A TP MCCB 25KA with spreader terminal and ROH- L&T/ GE Make preferred (subject suitable to rotary handle availability)	Nos	8		
s	Supply and Providing DP MCB 16A - L&T make	Nos	20		
t	Supply and Providing 35mfd Metal Can Capacitor (as per requirement APR)- for replacement of Weak and Damaged capacitors)	Nos	200		

Rupees:	0.00
---------	------

## Terms and Conditions

- Quantity as per final Measurements- Number of Bulbs and Other Spares.
- Change of Capacitor required as per the requirement. Weak and damaged capacitors to be replaced, as per approval and Quantity as per final Measurements.
- Supply and providing any other item other than mentioned ( which is quantable and to be invoiced) has to be placed for approval before installation. ( subject to approval matters).

