

<b>KERALA CRICKET ASSOCIATION</b>					
KCA COMPLEX, TC 24/131(1), Shasthamkovil Road, Thycaud, TRIVANDRUM -695014					
SCHEDULE OF WORK -1. Tender No. KCA/EL/01/2021 Sub Sch.3 dt.16.12.2021					
PREVENTIVE MAINTENANCE OF FLOOD LIGHTS AND CONNECTED ELECTRICAL SYSTEMS AT GREEN FIELD STADIUM THIRUVANANTHAPURAM					
SI No	Description	Unit	Qty	Rate	Amount
<b>UG CABLE RELAYING - SUBSTATION TO TOWER 4B/ CABLE CLAMPING</b>					
	<b>Cable Clamping</b>				
3.4	3C x 2.5sq.mm stranded Cu. Cable from ballast rack to Ignitor mounting box/lamp - Clamping of loose Cable to Provided Cable Tray using Cu wire as per site approval - 8 High Mast total	job	8		
	<b>Supply and Laying Charges - UG CABLE</b>				
3.5	<b>Supply , Laying Testing and Commissioning of 1 RUN 3.5 x 240sq.mm. XLPE Armoured Aluminium Cable. KEI/ FINOLOX</b>	m	300		
3.6	<b>SITC of 3.5 x 240 sq.mm. Al Armoured Cable Termination</b>	Nos.	2		
3.7	<b>Cable Trench - Excavation and Back filling of Cable Trench - 1000mm depth, 200mm bottom leveling/ 100mm sand -lay Cable- fill 150 mm Sand/ 50mm thick concrete tile, including fill 200mm back filling/ Marking tape and balance filling. (width- 300mm minimum as required)</b>	m	250		
Rupees:					
<p>Terms and Conditions</p> <ol style="list-style-type: none"> <li>1. Length of the Cable required/ Length of the Cable Trench as per Cable route finalisation and Quantity Subject to final Measurements.</li> <li>2. The Scheme for laying the Trench is as per Electrical Standard and to be as per provided.</li> <li>3. Any additional specification or requirements as per the site instructions shall be separate.</li> </ol>					