

KERALA CRICKET ASSOCIATION

Name of work : Miscellaneous Civil Repairs and Maintenance works to be executed on an urgent basis at Sports Hub, Kariavattom, Trivandrum in connection with upcoming T20 match India vs South Africa on 28 September 2022

QUOTATION SCHEDULE

Item No	Quantity	Unit	Details of work	Rate in figures	Unit	Rate in words	Amount
			APPENDIX A - CIVIL WORKS				
1	16.00	No	Closing the cable root opening in Light tower control rooms (60 x 30 x 20 cm), using Concrete cement block masonry (30 x 20 x 15 cm) with plastering in both sides of masonry, including cost of all materials, labour charges etc complete.		/no		
2	2.00	No	Cleaning the cable root opening in roof slab of light tower control rooms (100 x 75 x 12 cm), Concrete with cement concret 1:2: 4, using 20 mm graded brocken stone, plastering the concrete work in 12 mm thick, including cost of all materials, labour charges etc complete.		/no		
3	3.00	No	Correction of MS door with neccessary fittings (Levelling the MS outer frames, fixing frame and hinges, locking facilities etc, complete as per the directions of Engineer in charge		/no		
4	8.00	m2	Supplying and providing Aluminium powder coated wire mesh net with frame works (sliding) for ventilators with all fittings/ locking facilities etc, including cost of all materials, labour charges etc. complete as per the direction of Engineer in charge		/sqm		
			APPENDIX B - ROLLING SHUTTER				

5	56.00	No	Removing the shutter cover, greasing the rollers, channels, correcting locking facilities including cost of all materials, labour charges, hire charges for scaffolding etc. complete as per the direction of Engineer in charge,		/no		
			APPENDIX C - GLASS DOOR				
6	1.00	No	Main entrance 12 mm thick toughened glass sensor door re-conditioning works. (both side sliding)		/no		
7	57.00	No	12 mm thick toughened glass door service / re-conditioning works. in north pavlion area		/no		
8	5.00	m2	Providing and fixing 12 mm thick frameless toughened glass door of approved brand and manufacture, including providing and fixing top & bottom pivot & spring type fixing arrangement and making necessary holes etc. for fixing required door fittings, all complete as per direction of Engineer-in-charge		/sqm		
9	6.00	no	Providing and fixing 12 mm thick toughened glass door floor spring , Dorma or equivalent		/no		
10	6.00	no	Providing and fixing 12 mm thick toughened glass door lock , Dorma or equivalent		/no		
11	10.00	no	Providing and fixing 12 mm thick toughened glass top pivot , Dorma or equivalent		/no		
12	4.00	no	Providing and fixing 12 mm thick toughened glass door handle , Dorma or equivalent		no		
13	3.00	no	Removing and refixing existing 12 mm thick toughened glass door for proper opening in both sides etc.		no		

APPENDIX D - ALUMINIUM/ WOODEN DOOR							
14	44.00	no	Reconditioning Aluminium doors, change the glazing clips, pivots, proper opening condition, including cost of all materials, labour charges etc. complete as per the direction of Engineer in charge		/no		
15	19.00	no	Providing and fixing door closer in aluminium doors , Dorma or equivalent		/no		
16	11.00	no	Reconditioning wooden doors proper opening condition, labour charges etc. complete as per the direction of Engineer in charge		/no		
APPENDIX E - PARTITION WORKS							

17	40.00	m2	<p>Suspended Plain Ceiling includes Gypsteel ULTRA perimeter channel fixed along the perimeter of existing wall/ partition with the help of nylon sleeves and screws, at 610mm centres..Gypsteel ULTRA Ceiling Angle is suspended at desired height by fixing it to the soffit with Gyproc Soffit Cleat and Anchor Fastener creating 1220mm x 1220mm grid.. Gypsteel ULTRA Intermediate channel is fixed to the Gypsteel ULTRA Ceiling Angle with M6 Nut and bolt arrangement. The Gypsteel Ceiling Section is then fixed to the Gypsteel ULTRA Intermediate channel with the help of Gyproc Connecting Clip and in direction perpendicular to the Gypsteel ULTRA Intermediate channel at 457mm c/c..</p> <p style="text-align: center;">Single</p> <p>layer of 12.5mm tapered edge Gypboard Plain (conforming to IS 2095 Part 1:2011) is then screw fixed to ceiling section with 25mm drywall screws at 230mm centres.. Finally square and tapered edges of the boards are to be jointed and finished so as to have a flush look which includes filling and finishing with Gyproc Jointing Compound and Gyproc joint paper tape only (as per recommended practices of Saint-Gobain Gyproc India)</p>		/sqm		
----	-------	----	--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	--	------	--	--

18	13.00	m2	<p>97mm thick Gypsteel ULTRA stud partition which includes one layer of tapered edge 12.5mm thick Gypboard Plain (conforming to IS 2095 Part 1:2011) is screw fixed with GYproc drywall screws of 25mm at 300mm and 150mm at periphery of wall to either side of 70mm Gypsteel ULTRA C stud (0.5mm thick having one flange of 34mm and another flange of 36mm made of GI steel) placed at 610mm centre to centre in 72mm Gypsteel ULTRA floor and ceiling channel (0.5mm thick have equal flanges of 32mm made of GI steel). This is anchored to the floor and true ceiling using suitable anchor fasteners at 600mm in zigzag manner. Stud and floor channel are crimped together with crimping tool. The boards are to be fixed vertically to the framework with joints staggered to avoid leakage through joints. A Gypsteel ULTRA noggin channel of 700mm width (0.5mm thick having two flanges of 40mm each) has to be providing at the horizontal joints of the two boards screw fixed to the studs using Gyproc metal to metal flat head screws. Finally square and tapered edges of the boards are to be jointed and finished so as to have a flush look which includes filing and finishing with Gyproc jointing compound, Gyproc joint paper tape (as per recommended practices of Saint-Gobain Gyproc India). The junction of the partition with masonry and all penetration through the partition has to be treated</p>		/sqm		
19	17.00	m2	<p>Providing and fixing double side laminated hylam sheet for partition works, including all materials cost, labour charges etc. complete as per the direction of Engineer in charge</p>		/sqm		
APPENDIX F- MISCELLANEOUS WORKS							

20	2.00	m2	Providing and fixing polycarbon roof sheet extension works in players dressing room to ground passage, using aluminium 'L' angles, GP rectangular section and polycarbon sheets etc, including all materials cost, labour charges etc. complete as per the direction of Engineer in charge		/sqm		
21	4.00	m2	Providing and fixing of Premium Qualityceramic glazed floor tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.(Basic rate Rs.100/sq.ft)		/sqm		
22	1.00	no	Providing and fixing SS sink of size 150x60 cm with stand, two bowls, including cost and conveyance of all materials and labour charges etc, complete.		/no		
23	1.00	no	Providing and fixing 2 no of 20 mm thick water connection line and 63 mm thick waste water line connect the existing duct water line and waste connection in players kitchen, including cost and conveyance of all materials and labour charges etc, complete.		/no		
24	2.00	no	Supply & fixing brass C.P Kitchen zink tap with all accessories etc, complete (Jaquar, Cera or equilavalent)		/no		

25	56.00	no	Supply and fixing ceiling tiles of size 60x60 cm (Grid ceiling) and replacing the damaged tiles including cost and conveyance of all materials and labour charges etc, complete.		/no		
26	18.00	no	Providing water proofing by cementitious polymer application over the concrete surface by applying cement based two componets polymer modified water proofing slurry coating of such as Roffe, Fosroc, M.C. Bauchemie etc, after cleaning the surface free from rust, grease, oil etc, preparing the surface to be true and flat and saturated mixing the liquid (a) and powder (b) componets in the ratio 1:4 by weight. Applying in two coats with brush with an interval of 2 to 6 hour for hardening in between and finally finishing by rubbing down with sponge including protecting the applied surface from the direct sun light and strong wind and curing by damp gunny bags or polythene sheeting upto 5 days etc, including cost of conveyance of all materials at site, labour charges etc, complete.		/sqm		
27	1.00	no	Re conditioning the existing gate (Gate .no.02),greasing etc, including meterial and labour charges etc complete		/no		
28	1.00	/no	Re conditioning the existing gate (Gate .no.03), replace wheels,gate bottom MS square tube and damaged sections etc, including meterial and labour charges etc complete		/no		
29	288.00	m2	Finishing walls with Acrylic Smooth exterior paint of required shade: New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)		/sqm		

30	2.00	no	Supply and fixing CI manhole cover of size 60x60 cm (50 kg) medium duty,including cost and conveyance of all materials and labour charges etc, complete.		/no		
31	6.00	no	Re- conditioning the existing manhole cover of size 30x30 cm, MS / CI, welding, levelling and fixing in position,including cost and conveyance of all materials and labour charges etc, complete.		/no		
32	1.20	m2	Replace the damaged Mica sheet in players locker room -1, including cost and conveyance of all materials and labour charges etc, complete.		/sqm		
33	45.00	/no	Painting players room chairs with two coats enamel paint approved colour,including cost and conveyance of all materials and labour charges etc, complete.		/no		
34	2.00	no	Providing and fixing SS rod coat hooks (Model available in locker room)including cost and conveyance of all materials and labour charges etc, complete.		/no		
35	64.00	m2	Levelling and fixing existing PVC floor mat in players pavilion area, including cost and conveyance of all materials and labour charges etc, complete.		/sqm		
36	22.00	no	Supply & fixing brass C.P Angle cock with all accessories etc, complete (Jaquar, Cera or equilavalent)		/no		
37	70.00	no	Supply & fixing brass C.P Health fauset with all accessories etc, complete (Jaquar, Cera or equilavalent)		/no		

			Total				
						Add GST @ 18 %	
						TOTAL	
				Rounded to	Rs.		

Rupees in words :

Signature of
Contractor:
Name and address

Thiruvananthapuram:
Date :