

**KERALA CRICKET ASSOCIATION**

**NAME OF WORK : DISMANTLING THE EXISTING DAMAGED CHAIN LINK FENCING AND INSTALLATION OF NYLON FENCING NET AT WAYANAD  
CRICKET STADIUM, KRISHNAGIRI,WAYANAD**

**TENDER SCHEDULE**

Item No	Quantity	Unit	Details of work	Rate in figures	Unit	Rate in words	Amount
1	570.00	m2	Dismantling and removing PVC coated GI fencing net manually/ by mechanical means,including stacking of serviceable material and disposal of unserviceable materials to a place as per direction of Engineer-in-charge		/sqm		
2	385.00	m2	Removing earth from bottom of existing PVC coated GI fencing net work, for a width of 1 meter and depth of 100 mm, in excavation by mechanical means (Hydraulic excavator)/manual means over areas, including getting out and disposal of excavated earth lead upto 50 m, as directed by Engineer-in-charge.		/m		
3	1275.00	m2	Painting with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface scrapping and levelling to smooth even finish and sand papering etc. complete. On steel work as per the direction of Engineer in charge		/sqm		
4	740.00	m2	Providing and fixing 3 mm thick ( Black / Green colour ) HDPE Nylon net fencing of required width in mesh size 40x40 mm including strengthening with 1.50 mm thick twine etc complete as per the direction of Engineer-incharge		/sqm		
5	1300.00	m2	Providing and fixing 2.50 mm thick ( Black / Green colour ) HDPE Nylon net fencing of required width in mesh size 40x40 mm including strengthening with 1.50 mm thick twine etc complete as per the direction of Engineer-incharge		/sqm		

			TOTAL				
						Add GST @ 18 %	
						TOTAL	
				<b>Rounded to</b>	<b>Rs.</b>		

Rupees in words :

Signature of  
Contractor:

Name and address

Place :

Date :