

KERALA CRICKET ASSOCIATION

**NAME OF WORK: SETTING UP OF CORPORATE BOXES AT LEVEL -III AREA OF SPORTS HUB INTERNATIONAL STADIUM, KARYAVATTOM,
THIRUVANANTHAPURAM**

TENDER SCHEDULE

Item No	Quantity	Unit	Details of work	Rate in figures	Unit	Rate in words	Amount
			APPENDIX A - LEVEL III CORPORATE BOXES				
1	2000.00	sqm	Cleaning and removing the dust from ceiling and truss members with compressed air at level III corporate box area including all scaffolding, hire charges for all machineries and equipments, all labour charges etc. complete as per the direction of Engineer in Charge.		/sqm		
2	1500.00	sqm	Removing the waste materials from corporate box area level III and surroundings and disposing the waste to a distance more than 500 m from the cleaning area including cost of all labour charges, hire charges of vehicles and machineries for disposing etc complete as per the direction of Engineer in Charge.		/sqm		
3	750.00	sqm	Removing and carefully stacking the useful materials of KSFL(chairs, air condition accessories, roofing sheets etc.) to the rear side room of corporate box No.5 at level III including all labour charges etc. complete as per the direction of Engineer in Charge.		/sqm		
4	55.00	No	Removing the existing glass partition carefully with high attention and stacking the same to the rear side room of corporate box No.5 at level III including all labour charges etc. complete as per the direction of Engineer in Charge.		/No		

5	150.00	sqm	Chipping and removing the accumulated cement and concrete debris from the existing floor and disposing the waste to a distance more than 500 m from the cleaning area including cost of all labour charges, hire charges of vehicles and machinaries for disposing etc complete as per the direction of Engineer in Charge.		/sqm		
6	19.00	no	Fixing and aligning the pre-cast RCC structure for fixing chairs at front portion of all corporate boxes including all labour charges for aligning and fixing to the existing angle iron brackets, rectifying the damages of the existing brackets with welding and other works etc with necessary materials if required including all materials, labour charges etc. complete as per the direction of Engineer in Charge.		/no		
7	10.00	cum	Solid block masonry using pre cast solid blocks (Factory made) of size 30x20x15 cm or nearest available size confirming to IS 2185 part I of 1979 for foundation and plinth with thickness 15cm in: CM 1:6 (1 cement :6 coarse sand) etc		/cum		
8	180.00	sqm	15 mm cement plaster 1:3 (1 cement: 3 coarse sand) finished with a floating coat of neat cement on the rough side of single or half brick wall.		/sqm		

9	7500.00	kg	Structural steel work riveted, bolted or welded in built up sections or single sections, trusses and framed work with necessary MS angles, MS flats, 16 gauge GI rectangle tubes etc. including cutting, hoisting, fixing in position and applying two coats epoxy primer primer of approved quality including cost of all materials, labour charges etc complete as per the direction of Engineer in charge.		/kg		
10	360.00	sqm	Supplying, providing and fixing 18 mm thick calcium silicate cement board over the fabricated steel frame work, fixing with self screws including cost of all materials, labour charges etc complete as per the direction of Engineer in charge.		/sqm		
11	360.00	sqm	Providing and fixing 0.65 mm thick Vinyl flooring pasting the top side of players dressing room seating area (Covering the damage of Mica sheet) in both dressing rooms Including cost and conveyance of all materials to site labour charges etc, complete		/sqm		
12	1800.00	sqm	Finishing walls with Acrylic Smooth exterior paint of required shade: New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)		/sqm		
13	8.00	sqm	Providing and fixing 12 mm thick frameless toughened glass door of approved brand and manufacture, including providing and fixing top & bottom pivot & spring type fixing arrangement and making necessary holes etc. for fixing required door fittings, all complete as per direction of Engineer-in-charge		/sqm		

APPENDIX - B- LEVEL II CORPORATE BOX							
14	85.00	sqm	Partition with departmental glass including with all necessary fittings, fitting charges etc. complete as per the direction of Engineer in charge.		/sqm		
15	17.00	sqm	Providing and fixing 12 mm thick frameless toughened glass door of approved brand and manufacture, including providing and fixing top & bottom pivot & spring type fixing arrangement and making necessary holes etc. for fixing required door fittings, all complete as per direction of Engineer-in-charge		/sqm		
16	475.00	sqm	Finishing walls with Acrylic Smooth exterior paint of required shade: New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)		/sqm		
			Total				
						Add GST @ 18 %	
						TOTAL	
				Rounded to	Rs.		

Rupees in words :

Signature of Contractor:

Thiruvananthapuram:

Name and address:

Date :