

ANNEXURE A - DATA LINE SERVICE REQUIREMENT

SN	Installation Area	Primary Connection	Secondary Connection	Remarks
1	Media Box	1:1 ILL with 500 Mbps with 3 wifi modems to serve upto 150 concurrent users	300 Mbps FTTH	
2	Photographer's Area	1:1 ILL with 500 Mbps with 2 wifi modems to serve upto 60 concurrent users	300 Mbps FTTH	
3	Press Conference Hall	1:1 ILL with 100 Mbps with 1 wifi modem to serve upto 10 concurrent users	Nil	
4	BCCI Photographer 1	1:1 ILL with 100 Mbps with 1 wifi modem to serve upto 3 concurrent users	100 Mbps FTTH	
5	BCCI Photographer 2	1:1 ILL with 100 Mbps with 1 wifi modem to serve upto 3 concurrent users	100 Mbps FTTH	
6	BCCI Official in front of PMOA	1:1 ILL with 100 Mbps with 1 wifi modem to serve upto 3 concurrent users	Nil	
7	Gates	25 x 30 Mbps FTTH connections wifi modems to serve upto 5 concurrent users in each connection	Assured backup to each connection	
8	Commentary Box	1:1 ILL with 2x100 Mbps with 3 wifi modems to serve upto 15 concurrent users	100 Mbps FTTH	
9	Studio	1:1 ILL with 100 Mbps with 1 wifi modem to serve upto 5 concurrent users	100 Mbps FTTH	
10	BCR – I	2 x 1:1 ILL with x100 Mbps with 4 wifi modems & 1 AP to serve upto 30 concurrent users PLUS two 1:1 ILL with x100 Mbps wired connections to serve upto 10 devices	3 x 300 Mbps FTTH	
11	BCR – II	2 x 1:1 ILL with x100 Mbps with 4 wifi modems & 1 AP to serve upto 30 concurrent users PLUS two 1:1 ILL with x100 Mbps wired connections to serve upto 10 devices	3 x 300 Mbps FTTH	From 5th to 15th January
12	First Floor North Pavilion (For MR, 3rd Umpire, Video Analyst)	3 x 1:1 ILL with 50 Mbps with 3 wifi modem to serve upto 5 concurrent users	100 Mbps FTTH	From 5th to 15th January
13	Player's Dining Area	1:1 ILL with 50 Mbps with 1 wifi modem to serve upto 10 concurrent users	100 Mbps FTTH	
14	Office	300 Mbps FTTH with 1 wifi modem to serve upto 15 concurrent users	100 Mbps FTTH	From 5th to 15th January
15	Police Control Room	1:1 ILL with 100 Mbps with 1 wifi modems to serve upto 50 concurrent users	Nil	
16	Scorer	100 Mbps FTTH	Nil	

VOICE LINE SERVICE REQUIREMENT

SN	Installation Area	Connectivity and Numbers	
1	North Pavilion Ground Level	STD Lines - 7 Numbers	
		ISD Lines - 2 Numbers	
2	Media Box	Fax Line with STD - 1 Number	

Standby for Termination Equipments should be Made Available for all Main Terminations

Installation & Commissioning of Total System - 11th January 2023

Sufficient numbers of experienced technicians and supervisors should be made available throughout during the period of engagement