

KERALA CRICKET ASSOCIATION					
KCA COMPLEX, TC 24/131(1), Shasthamkovil Road, Thycaud, TRIVANDRUM -695014					
SCHEDULE 3					
PRE MATCH MAINTENANCE OF FLOOD LIGHTS AND CONNECTED ELECTRICAL SYSTEMS AT GREEN FIELD STADIUM THIRUVANANTHAPURAM					
SI No	Description	Unit	Qty	Rate	Amount
PRE MATCH MAINTENANCE AND REPLACEMENT OF DAMAGED BULBS, IGNITORS, CAPACITORS					
1.0	Flood Light Units				
1.1 (a)	BULB REPLACEMENT - Checking the Flood light units - Changing the Bulbs as per requirement, testing and commissioning as required.	Nos.	100.000		
Floodlight Components					
1.1.1	Checking the Capacitor value - for the installed capacitor and identifying the weak capacitors to be replaced.	Nos.	824.000		
1.1.2	Capacitor replacements - Checking the status of the capacitors (total of 824), replacing the weak /damaged/ exploded capacitors in the floodlight panel.	Nos.	180.000		
1.1.3	Replacing the Ignitors for floodlights - Installed with the floodlight fixtures at the highmast.	Nos.	100.000		
1.2	Checking the cables from Tower electrical room to floodlights/ Main electrical panel at the Tower control room to Ballast / Capacitor panel etc., replacing damages, Clearing the short circuit cables, Insulation damages etc. Checking the contact blocks and clearing the damages.				
1.2.1	3C x 2.5sq.mm stranded Cu. Cable from lighting panel to ballast rack with terminations	Set	412		
1.2.2	3C x 2.5sq.mm stranded Cu. Cable from ballast rack to Ignitor mounting box/lamp with Terminations	Set	412		
Rupees:					
<p>Terms and Conditions</p> <p>SCHEDULE 3 IS FOR LABOUR PART AND SUPPLY OF MATERIALS NOT INCLUDED IN THE SCOPE</p> <p>1. Item number 1.1(a), 1.1.2, 1.1.3 are subject to final measurements at site.</p> <p>2. Item number 1.1.1, 1.2.1, 1.2.2 are required quantity and shall be calculated as lumpsum for the specified work executed</p> <p>3. Change of Capacitor required as per the requirement. Weak and damaged capacitors to be replaced.</p>					