

KERALA CRICKET ASSOCIATION**NAME OF WORK: PAINTING AND ALLIED WORKS AT WAYANAD CRICKET STADIUM, KRISHNAGIRI,WAYANAD.****TENDER SCHEDULE**

Item No	Quantity	Unit	Details of work	Rate in figures	Unit	Rate in words	Amount
1	5500.00	sqm	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete		/sqm		
2	5500.00	sqm	Finishing walls with Acrylic Smooth exterior paint of required shade : Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface		/sqm		
3	4000.00	sqm	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete on steel works as directed by the Engineer in charge		/sqm		
4	300.00	sqm	Painting with synthetic enamel paint two coat with quality pints approved by the Engineer in charge after scrapping and sand papering, levelling to smooth even finish including cost and conveyance of all materials to site, labour charges, hire and labour charges of scaffolding etc,complete for structural steel sections as directed by the Engineer in charge		/sqm		
5	300.00	sqm	Cleaning glazed doors, windows and ventilators both side with glass cleaning liquid / soap liquids etc, including cost and conveyance of all cleaning materials to site, labour charges, hire and labour charges of scaffolding etc,complete for all glazed sections as directed by the Engineer in charge		/sqm		

Item No	Quantity	Unit	Details of work	Rate in figures	Unit	Rate in words	Amount
6	50.00	m	Supplying & fixing 200 mm dia or nearest available size PVC Rain Water Gutter pipes, PVC Rain water system, to connect half round section fitted with deep rubber Gasket and clips must be screwed directly to fascia or anchored by a suitable rafter bracket. The details of fittings are pipe support bracket, stop end etc. Including cost and conveyance of all fittings and materials to site, labour charges etc. complete.		/m		
			TOTAL				
						Add GST @ 18 %	
						TOTAL	
				Rounded to	Rs.		

Rupees in words :

Place:
Date :Signature of Contractor:
Name and address