

## **KERALA CRICKET ASSOCIATION**

**NAME OF WORK : REPLACING THE DAMAGED CHAIN LINK SURROUND FENCING WITH GI SQUARE TUBES AND 3 mm BRAIDED NYLON NET  
AT SD COLLEGE CRICKET GROUND**

### **TENDER SCHEDULE**

Item No	Quantity	Unit	Details of work	Rate in figures	Unit	Rate in words	Amount
1	460.00	m2	Dismantling the existing chain link fencing care fully and stacking the same within a lead of 200 m including cutting, loading, unloading, transporting, etc complete as per the direction of Engineer-in-charge		/m2		
2	3.00	m3	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in-charge.		/m3		
3	44.00	m3	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains, including dressing of sides and ramming of bottoms, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m and lift upto 1.5m.		/m3		
4	145.00	m2	Centering and shuttering including strutting, propping etc. and removal of form work for Foundations, footings, bases for columns		/m2		
5	9.50	m3	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level: 1:2:4 ( 1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)		/m3		
6	2.00	m3	Solid block masonry using pre cast solid blocks (Factory made) of size 30x20x15 cm or nearest available size confirming to IS 2185 part I of 1979 for foundation and plinth with thickness 15cm in: CM 1:6 ( 1 cement :6 coarse sand) etc		/m3		

Item No	Quantity	Unit	Details of work	Rate in figures	Unit	Rate in words	Amount
7	20.00	m2	15 mm cement plaster on rough side of single or half brick wall of mix: 1:4 (1 cement: 4 coarse sand)		/m2		
8	3335.00	kg	Frame work in built up tubular (round, square or rectangular 16 gauge hollow GI tubes etc. ) including cutting, hoisting, fixing position and applying a priming coat of approved metal primer, including welding and bolted with special shaped washers etc. complete. (Hot finished welded type tubes)		/kg		
9	10.00	m2	Painting with Synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work		/m2		
10	235.00	m2	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete. on steel works		/m2		
11	490.00	m3	Providing and fixing 40 mm square pattern 3.mm braided black/green nets tying with 3 mm toins, fixing in rectangle frames already fixed including cost of all materials, labour charges etc. complete.		/m3		
			<b>TOTAL</b>				
						Add GST @ 18 %	
						TOTAL	

**Rounded to Rs.**

Rupees in words :

Place :

Date :

Signature of  
Contractor:

Name and adress