KERALA CRICKET ASSOCIATION

Development of Twin Outdoor Concrete Cricket Wickets with Practice Net Facilities at Alphonsa College, Pala, Kottayam

Tender Schedule

Sl No	Qty	Unit	Item Description	Rate (in Figures)	Unit	Rate (in Words)	Amount
1	28.00	cum	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.		/cum		
2	140.00	cum	Filling with contractor's own earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5 m as per direction of site Engineer-in-charge		/cum		
3	12.00	sqm	Centering and shuttering including strutting, propping etc. and removal of form for foundations, footings, bases of columns, etc. for mass concrete		/sqm		
4	20.00	cum	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)		/cum		
5	14.00	cum	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:1½:3 (1 Cement: 1½ coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)		/cum		
6	15.00	cum	Providing and laying C.C. pavement Of mix M-25 With ready mixed concrete from batching plant/site batching. The concrete shall be laid and finished With screed board vibrator , vacuum dewatering process and finally finished by floating, brooming With Wire brush etc. complete as per specifications and directions Of Engineer-in-charge.		/cum		

Signature of Contractor

Tender Schedule

Sl No	Qty	Unit	Item Description	Rate (in Figures)	Unit	Rate (in Words)	Amount
7	350.00	kg	Steel reinforcement for R.C.C. work including straightening, cutting, bending,placing in position and binding all complete upto plinth level - Thermo-Mechanically Treated bars of grade Fe-500D or more.		/kg		
8	1800.00	kg	Providing and fixing rail of approved size by welding etc. to steel ladder railing, balcony railing, staircase railing and similar works, including applying priming coat of approves steel primer. G.I. pipes		/kg		
9	15.00	sqm	Providing and fixing G.I. chain link fabric fencing Of required Width in mesh size 50x50 mm including strengthening With 2 mm dia Wire or nuts, bolts and washers as required complete as per the direction Of Engineer-in-charge. Made Of G.I. Wire Of dia 4 mm		/sqm		
10	76.00	sqm	Painting With synthetic enamel paint Of approved brand and manufacture to give an even shade : Two or more coats on new work		/sqm		
11	800.00	sqm	Supply and installation of Matsyafed HDPE sports netting, manufactured from high-strength HDPE yarn, 2.0 mm nominal diameter/thickness, with 50 × 50 mm mesh size,Green/Black, as approved, suitable for outdoor cricket practice applications. Net shall be UV-resistant, weather-resistant, rot-proof and suitable for continuous outdoor exposure. The rate shall include cutting, stitching/hemming, fixing and tensioning, including all necessary supporting hookes, binding ropes, clamps,ties, fasteners and other accessories required for a neat and secure installation, complete as directed by the Engineer-in-Charge.		/sqm		
12	3.00	cum	Solid block masonry using pre cast solid blocks (Factory made) of size 30x20x15 cm or nearest available size confirming to IS 2185 part I of 1979 for foundation and plinth with thickness 15cm in: CM 1:6 (1 cement :6 coarse sand) etc complete		/cum		

Signature of Contractor

Tender Schedule

Sl No	Qty	Unit	Item Description	Rate (in Figures)	Unit	Rate (in Words)	Amount
13	30.00	sqm	12 mm cement plaster Of mix : 1:4 (1 cement: 4 fine sand)		/sqm		
14	30.00	sqm	Applying priming coats With primer Of approved brand and manufacture, having IOW VOC (Volatile Organic Compound) content.With water thinnable cement primer on wall surface having VOC content less than 50 grams/liter		/sqm		
15	3.60	sqm	Fabricating, supplying and fixing of outdoor name board, comprising projected acrylic letters of upto 500 mm height including KCA logo, complete with required back support with 50 × 25 mm GI rectangular hollow-section supporting frame, fabrication, cutting, welding/joints, brackets, fasteners, necessary supports, enamel painting with steel primer, erection , complete in all respects as directed by the Engineer-in-Charge.		/sqm		
			Total				
			GST				
			Total (Incl of GST)				

Rupees in Words:

Sign & Seal of Contractor

Place :

Name & Address:

Date:

Signature of Contractor